



METALWORKS™ Plank *Custom looks with Standard Products*

Hook-on
smooth texture

CAD/Revit® drawings at:
armstrongceilings.com/cadrevit



▲ MetalWorks™ Plank Microperforated panel in Silver Grey


See more photos at:
armstrongceilings.com/photogallery
SEARCH: metalworks plank

Durable, steel hook-on planks with 1/8" reveal.


KEY SELECTION ATTRIBUTES

- Crisp visual with narrow 1/8" reveal
 - Good NRC with acoustical fleece (perforated pattern)
 - Economical option with fast delivery
- new** • Select products included in the FAST134 program – ready to ship in 4 weeks or less
- Durable – Washable, Scrubbable, Impact-resistant, Soil-resistant

COLORS Due to printing limitations, shade may vary from actual product.



PERFORATION OPTIONS (1:2 scale shown)



DETAILS



MetalWorks Plank Microperforated

TechLine 877 276-7876
armstrongceilings.com/metalworksplank

METALWORKS™ Plank

Hook-on
smooth texture

LEED® WELL™ | LBC

UP TO **25% RECYCLED CONTENT**

- energy management
- construction waste mgmt
- regional materials
- design for flexibility
- EPD
- recyclable/producer resp.
- biobased materials
- recycled content
- sourcing of raw materials
- material ingredient reporting
- low emitting materials
- lighting quality
- acoustics

Calculate sustainability with GreenGenie™ armstrongceilings.com/greengenie

LOCATION DEPENDENT

WITH INFILL PANEL

VISUAL SELECTION

| Item No. ♦ | Dimensions Nominal W x L (Inches) | Perforations |
|-------------------|---|--------------|
| METALWORKS™ Plank | | |
| 5330__ | 16" x 72" | M1 |
| 5331__ | 16" x 72" | M2 |
| 5332__ | 16" x 96" | M1 |
| 5333__ | 16" x 96" | M2 |



FAST
4 WEEKS
or Less

FAST134 program items ready to ship from manufacturer in 4 weeks or less.
Up-to-date lead times and product options (sizes and colors) at armstrongceilings.com/fast134.

♦ When specifying or ordering, include the appropriate two-digit color suffix with the item number (e.g., 5330 W H; 5332 S G).
Light reflectance is for White only.

PERFORMANCE

Dots represent high level of performance.

| Fire Performance | Light Reflect (White only) | DURABILITY | | | |
|------------------|----------------------------|------------|-------|--------|------|
| | | Wash | Scrub | Impact | Soil |
| Class A | 0.73 | • | • | • | • |
| Class A | N/A | • | • | • | • |
| Class A | 0.73 | • | • | • | • |
| Class A | N/A | • | • | • | • |

ACOUSTICAL INFORMATION

| Perforation | NRC | CAC |
|-----------------------|--------|-----|
| M1 Unperforated | N/A | 36 |
| M2 Microperforated | 0.70** | 31* |

* With optional field-cut #747 mineral fiber backing. For more information on acoustical infill panels, visit armstrongceilings.com/mwaccessories

** With acoustical fleece only

ACCESSORIES

| Item No. ♦ | Description | Length | Pieces/Carton |
|------------|-----------------------------------|--------|---------------|
| 5336__ | 4-1/2" Plank Trim | 10' | 5 |
| 5337 | Seismic Spring | N/A | 100 |
| M311081 | Pressure Spring | N/A | 100 |
| M330011A | F Shadow Gap Wall Angle RA5F – WH | 10' | 10 |
| M330003A | F Wall Angle RA4F – WH | 10' | 10 |
| M330005A | F Wall Angle RA4F – SG | 10' | 10 |

SUSPENSION SYSTEMS

| Item Number | Description | Length | Pieces/Carton |
|-------------|----------------------------------|--------|---------------|
| HD8906 | 12' Heavy-duty Drywall Main Beam | 12' | 12 |
| 5335 | 4' Hook-on Cross Tee Assembly | 4' | 10 |

PHYSICAL DATA

Material
Electrogalvanized steel – thickness 0.028"

Surface Finish
Factory-applied, powder-coated finish (post-coated)

Fire Performance
Class A: Flame Spread Index 25 or less. Smoke Developed Index 50 or less.

Design Considerations
If non-standard sizes, colors, or perforations are needed, call 1 877 276-7876 for TechLine, or contact your Armstrong Ceilings representative to review the MetalWorks™ RH200 Custom Plank system. Install with minimum plenum clearance.

Installation Consideration
Cut panels are non-accessible.

Recommended Suspension System
Drywall Heavy-duty main beams with MetalWorks™ Plank Hook-on cross tees, as listed above.

Seismic Restraint
MetalWorks™ Plank have been engineered, tested, and approved for application in all seismic areas, when installed per Armstrong Ceilings installation instructions.

FAST134 Program Considerations
Size of Job Matters: Big jobs, over 2500 SF or 50 pieces for shapes/vertical elements will have longer lead times.

Location Matters: Transit time not included. We are ready to ship in 1 week on FAST1 items. However, transit to the states west of Wyoming may add time.

Distributor Truck Schedule Matters: We rely on distribution to help move products around the country. When speed matters, work with your local distributor to ensure FAST134 service.

Stock vs Made-to-Order Matters: FAST3 & FAST4 items are made-to-order and will ship direct to distributor. FAST1 (stocked items) will go through distribution and depend on distributor truck schedules.

Warranty
Details at armstrongceilings.com/warranty

Weight; Panels/Carton
0.88 lbs/SF; 4 panels/ctn